



MILLS PARK - UPDATE
Oak Park, IL

MASTER PLAN

(P) Consider widening the path 12" to 18" on each side;
Add raised curb to retail mulch and protect beds;
Add 18" conc walk behind curb; Replace concrete at
edge of driveway.

(P) Move trash enclosure away from historic fence and
entry. Replace with a more appropriate design.
If it cannot be moved or replaced, paint timber black
or use new composite wood to match the fence.

(P) Aerate soil & resod

(P) Potential to Restore & Reinstall Fence
Along Western Edge

(P) Remove soil, replace concrete and
raise curb.

(P) Consider concrete pad. Add planting to
frame and block views. Top-dress soil
and aerate and reseed or resod.

(P) Adjust Grading of 3' Soft Surface Trail

(P) Remove existing
shrubs and replant
along the N side &
NE edges

(P) Restore Steps &
Entry Metal Work.

(P) Adjust Flood Lights
So As Not To Shine
On Adjacent Resi-
dences.


(P) Potential Restoration
of Historic Fountain

(P) Replace Historic
Chestnut Tree

(P) Consider Sculpture
in the Park

(P) Expand Woodland Discovery Area

(P) = Proposed Improvements May 2017



<p>DATE: 5.31.17 DRAWN BY: JS CHECKED BY: JBJ/JM SCALE: 1" = 20' Stamp: EXP</p>	
<p>North</p>	
<p>L-1 Sheet Number</p>	

